

OFFERING MEMORANDUM

Contractor Bay

Units 1&2 Available for Sale or Lease



Commercial
Realty Advisors
KEVIN PEPE
Office: 508-862-9000, ext. 105
KPepe@comrealty.net



**NEW CONSTRUCTION
COMPLETED AUGUST 2024**

68 Mercantile Way, Units 1 & 2

FOR SALE OR LEASE

AREA


MASHPEE, MA

\$999,000 (SALE)
\$4,800/mo (NNN - LEASE)

+/- 2,400 sq. ft.
Double Unit


PROPERTY LOCATION



68 Mercantile Way, Mashpee, MA 02649



PROPERTY LOCATION

68 Mercantile Way, Mashpee, MA 02649







Interior Photos

68 Mercantile Way, Mashpee, MA 02649



Interior Photos

68 Mercantile Way, Mashpee, MA 02649



Exterior Photos


68 Mercantile Way, Mashpee, MA 02649



Available for sale or lease, this brand-new commercial business bay, located at **68 Mercantile Way, Mashpee, MA**, offers an excellent opportunity for businesses seeking a prime location. The **2,400 sq. ft. double unit**, with 2-14' overhead doors, 4 personnel doors, multiple offices and two rest rooms. Available at **\$4,800 per month (NNN)** or for sale at **\$999,000**, the property is suitable for a variety of commercial uses.

Conveniently situated near the commercial hub of Mashpee, including **Mashpee Commons**, the property provides easy access to **Massachusetts Routes 28 and 151**, facilitating quick connections to the **Bourne Bridge** and the **Mid-Cape area** via Route 28 (Falmouth Road).

Recently constructed and completed in **August 2024**, this flexible space can be leased collectively or potentially divided to suit your business needs. For inquiries, please contact **Kevin Pepe** at **508-862-9000, ext. 105**.



ZONING TABLE		
ZONING DISTRICT: I-1 (Industrial District)		
OVERLAY DISTRICTS: LIGHT INDUSTRY OVERLAY DISTRICT		
ALLOWED USE: WAREHOUSE	PROPOSED USE: -- (B) CONTRACTOR BAYS**	
EXIST USE: VACANT	PROPOSED BUILDING:	8,972 SF
	1-STORY WAREHOUSE	8,972 SF
	TOTAL BUILDING FLOOR AREA	8,972 SF
LOT AREA=142,346 SF (3.27± AC)		
MIN. LOT AREA	REQUIRED/ALLOWED	PROVIDED/PROPOSED
40,000	40,000	142,346 SF
FRONTAGE	200 FT	332 FT (MERCANTILE WAY)
FRONT SETBACK	75 FT	164.9 FT
SIDE SETBACK	30 FT (50' FROM RES.)	60.1 FT
REAR SETBACK	50 FT	55.1 FT
PARKING AREA SETBACK TO PROPERTY	10 FEET	10.0 FT
LANDSCAPE TO PARKING RATIO:	1:5	20.6%
MAX. BLDG. HEIGHT (STORIES)	2 STORIES/35 FEET	1 STORY/29.5 FEET
MAX. % LOT COVERAGE (STRUCTURES)	25% (35,587± SF)	7.0% (8,972 SF)
PARKING TABLE	WAREHOUSE (1/900 SF GFA) = 9972/900	11.1 SPACES
TOTAL PARKING	11 SPACES	11 SPACES
HANDICAP PARKING (TOTAL/VAN)	1/1	1/1
DESIGN VEHICLE		AASHTO BU

**REQUIRES SPECIAL PERMIT FROM ZBA.

NOTES:

1. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH MASS. TOWN ORDINANCES, REQUIREMENTS, AND SPECIFICATIONS.
2. THE CONTRACTOR SHALL CONTACT THE ENGINEER TO SCHEDULE A PRE-CONSTRUCTION MEETING AT LEAST TWO (2) WEEKS PRIOR TO COMMENCING CONSTRUCTION.
3. THE CONTRACTOR SHALL MAKE SUBMITTALS TO THE ENGINEER FOR APPROVAL BEFORE ANY FABRICATION OR DELIVERY OF PRODUCTS OR MATERIALS.
4. ALL PROPOSED WALKWAYS SHALL BE HANDICAPPED ACCESSIBLE WHERE REQUIRED. ALL PROPOSED RUNNING SLOPES OR WALKWAYS SHALL BE LESS THAN 5% AND ALL CROSS SLOPES < 2%. THERE ARE MAXIMUM SLOPES WITH NO TOLERANCE. ALL WORK WILL BE IN ACCORDANCE WITH THE MOST CURRENT REQUIREMENTS OF THE U.S. ACCESS BOARD, AMERICANS WITH DISABILITIES ACT & COMMONWEALTH OF MASSACHUSETTS, ARCHITECTURAL ACCESS BOARD.
5. CONTRACTOR SHALL CONFIRM AND PROVIDE ALL LANDINGS OUTSIDE OF DOORWAYS AT THE TOP AND BOTTOM OF STEPS, AND AT TOP AND BOTTOM OF RAMP, TO BE CONSTRUCTED SO THE LANDING IS 5 FT X 5 FT MIN. (100) AND IS LESS THAN A 2% SLOPE IN ALL DIRECTIONS ON THE LANDING.
6. DEMOLISH/REMOVE ALL EXISTING STRUCTURES, FOUNDATIONS, CONCRETE PADS, FENCES AND APPURTENANCE ITEMS UNLESS OTHERWISE NOTED TO SAVE. GRAVE OR BURY EXISTING PAVEMENT IN AREA OF PARKING WHERE ASPHALT IS STRUCTURALLY SOUND, SHOWS NO SIGN OF CRACKING, AND MEETS PROPOSED GRADIES SHOWN ON GRADING PLAN.
7. EXISTING PAVING EDGES SHALL BE SAWCUT TO CREATE A CLEAN EDGE WHERE IT IS TO BE TIED INTO NEW PAVING, OR WHERE ASPHALT IS REMOVED ADJACENT TO ASPHALT WHICH IS TO REMAIN. WIDTH OF UNPAVED APPROXIMATE SHALL BE REQUIRED AND SURFACE REPLACED WITH SUITABLE COMPACTED MATERIAL PER PAVEMENT SECTION DETAIL HEREIN. ANY SAWCUT LINES SHOWN ON THE PLANS ARE APPROXIMATE ONLY. THE EXACT EDGE OF SAWCUT SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD TO PROPERLY BLEND TO THE SURROUNDING GRADIES. PROPOSED ASPHALT SHALL BE PROPERLY BUTTED AND BLENDED TO SURROUNDING ASPHALT WHICH IS TO REMAIN. THE BLENDED TRANSITION BETWEEN PROPOSED AND EXISTING ASPHALT SHALL BE WITH AN APPROXIMATE 1.5% GRADIE UNLESS OTHERWISE IDENTIFIED. THE JOINT SHALL NOT BE ABRUPT.
8. DIMENSIONS SHOWN ARE TO OUTSIDE FACE OF FOUNDATION OR TO THE FACE OF CURB/BERM WHERE APPLICABLE. SETBACKS TO PROPERTY LINES SHOWN ARE FOR THE PROPERTY LINE SET BY THE REGISTERED PROFESSIONAL LAND SURVEYOR (PLS) AS SHOWN ON THE EXISTING CONDITIONS PLAN AS SEALED BY THE PLS WITHIN THIS PLAN SET.
9. ALL CURBING SHALL BE INSTALLED SO THAT WHEN A TERMINAL END OF A CURB EXISTS IT SHALL HAVE A TAPERED END PER MOST SPECIFICATIONS SO THAT THERE IS NOT A BLUNT SQUARE END PROTRUDING.
10. THE CONTRACTOR SHALL NOTIFY AND COORDINATE A SITE MEETING WITH THE ENGINEER PRIOR TO FINISHING FINAL PAVING COURSE (LS). LOT AND AREA SHALL BE REQUIRED DIMENSIONS ARE TO BE REVIEWED AT THIS MEETING PRIOR TO PAVING OPERATION. REQUIREMENTS SHALL BE PER MASSDOT STANDARD SPECIFICATIONS.
11. ALL PAVEMENT MARKINGS AND STRIPING SHALL FOLLOW MAUSD STANDARDS. TYPICAL LINE WIDTH FOR LANE AND PARKING STRIPING SHALL BE 4 INCHES UNLESS OTHERWISE NOTED. PARKING STRIPING SHALL BE WHITE, TYPICAL, UNLESS OTHERWISE NOTED.
12. BUILDING AND SITE SIGNAGE SHALL MEET REQUIREMENTS OF TOWN ZONING AND/OR SIGN ORDINANCES.
13. ALL WORK WITHIN THESE PLANS SHALL BE PERFORMED AND PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH THE CONSTRUCTION DETAILS PROVIDED IN THIS PLAN SET WHETHER OR NOT THE DETAIL NUMBER IS SPECIFICALLY REFERENCED.

SIGN SUMMARY			
M.U.T.C.D. NUMBER	SPECIFICATION	TEXT	QUANTITY
HC*	12" 18"	SEEDED PAVING	1
RT-1	24" 24"	STOP	1

SIGN INSTALLER SHALL COORDINATE SPECIFIC SIGN INFORMATION AND WORKING REQUIREMENTS WITH LOCAL AGENCIES AS NECESSARY.

ALL SIGNAGE MUST BE IN CONFORMANCE WITH THE FEDERAL HIGHWAY ADMINISTRATION "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD), LATEST EDITION, ALL APPLICABLE CODES, AND LOCAL REQUIREMENTS. LOCAL REQUIREMENTS, WHEN THEY EXIST, SHALL SUPERSEDE MUTCD.

- * ADD "VAN ACCESSIBLE" WHERE APPROPRIATE
- * COLOR AND WORDING PER LOCAL REQUIREMENTS

FOR PERMIT ONLY - NOT FOR CONSTRUCTION

BAXTER NYE
ENGINEERING & SURVEYING

BAXTER NYE
ENGINEERING & SURVEYING

Registered Professional Engineers and Land Surveyors

78 North Street - 3rd Floor
Hyannis, Massachusetts 02601

Phone - (508) 771-7502
Fax - (508) 771-7622
www.baxter-nye.com

STAMP STAMP

CONSULTANT

CONSULTANT

PREPARED FOR:
Daniel Hostetter
7 Parker Road
Osterville, MA 02655

PROJECT TITLE
Proposed Contractor Bays
68 Mercantile Way
Mashpee, MA 02649

DATE DESCRIPTION

SHEET TITLE

Site Layout Plan

SHEET NO

C3.0

DATE: MAY 17, 2022

SCALE: 1"=20'

DRAWN BY: **ML** CHECKED BY: **WKE**
JOB NO: 2022-007 FILE: 2022-007 ML.dwg



About

Commercial Realty Advisors, Inc. specializes in commercial and industrial real estate, mergers, acquisitions, joint ventures, divestitures, and other business broker strategies. It is a commercial and real estate brokerage based in Hyannis, Massachusetts, specializing in middle-market transitions. The culture of our firm is that of an investment bank with a premium placed on intellectual vitality, relationship management, and knowledge of geographic markets. A cadre of well-educated and successful experts partner with clients to achieve objectives in a cost and time- effective manner. Our business is broadly based. Our real estate practice includes development, investment, and other commercial sale, lease, and management arrangements. Transactions include manufacturing, retailing, food processing, restaurant and hospitality, golf course, marinas, and other businesses.

Commercial Realty Advisors' Disclaimer

This information has been secured from sources we believe to be reliable, but we make no representation or warranties, expressed or implied, as to the accuracy of the information contained herein. Commercial Realty Advisors, Inc. and the agent presenting this opportunity represent the Seller / Lessor, and are neither architects, engineers, inspectors, accountants nor attorneys, and therefore all buyers / tenants must consult with their own architects, engineers, inspectors, accountants or attorneys as to financial, zoning, lot line, handicapped accessibility, flood plain, mechanical, structural, or environmental concerns. Buyer must verify all information and bears all the risk for inaccuracies. Referenced square footage and acreage and sketched outlines are approximate, and this information package is subject to change.

COMMERCIAL REALTY ADVISORS

222 West Main St.
Hyannis, MA
508-862-9000 | comrealty.net

KEVIN PEPE

Office: 508-862-9000, ext. 105
KPepe@comrealty.net

LICENSE #6295

